

Bar Bending Schedule

Reinforcement Detail Report

Project	Hospital Block C
Client	City Trust
Element	Slab
Date	05 May 2026
Prepared by	XYZ Engineering

For Construction Use

Final check by qualified structural engineer required before fabrication.

Project Details

1. Element & Dimensions

Parameter	Value	Parameter	Value
Element Type	Slab	Shorter Span	3500 mm
Longer Span	5000 mm	Clear Cover	20 mm

2. Reinforcement Details

Parameter	Value	Parameter	Value
Main Bar Dia	10 mm	Main Bar Spacing	150 mm
Distribution Bar Dia	8 mm	Distribution Bar Spacing	200 mm
Hook Type	135°	Lap Length	0 mm

3. Calculation Settings

Parameter	Value	Parameter	Value
Quantity Mode	Standard	Standards	IS 456:2000, IS 2502:1963
Wastage Factor	5% (industry default)	Standard Rod	12 m

Bar Bending Schedule (BBS)

Element: **Slab** | Total bars: 52 | Net weight: 112.08 kg

Bar Mark	Element	Description	Dia (mm)	Cutting Len (mm)	Qty	Total Len (m)	Weight (kg)
M1	Slab	Main Bar (along shorter span)	10.0	3660.0	34	124.44	76.81
D1	Slab	Distribution Bar (along longer span)	8.0	4960.0	18	89.28	35.27
TOTAL						213.72	112.08


✓ **Engineering Verified** — Independent recalculation of total_length & weight per row.

Bar Shape Drawings

Schematic drawings of every bar in the schedule. Numbers next to each shape are exact mm dimensions. *Drawings are not to scale.*

M1 — Main Bar (along shorter span)


Main Bar (along shorter span)
■10 mm hook: 135° (100 mm = 10·d)



Dia: 10.0 mm · Cutting length: 3660.0 mm · Quantity: 34 · Weight: 76.81 kg

D1 — Distribution Bar (along longer span)

Distribution Bar (along longer span)
■8 mm straight (no hooks)



Dia: 8.0 mm · Cutting length: 4960.0 mm · Quantity: 18 · Weight: 35.27 kg

Final Steel Order Summary

Diameter-wise grouping with 5% wastage applied. Standard rod length = 12 m. Hand this directly to your supplier.

Diameter (mm)	Net Length (m)	Net Weight (kg)	Wastage %	Order Length (m)	Order Weight (kg)	12 m Rods
8.0	89.28	35.27	5%	93.74	37.03	8
10.0	124.44	76.81	5%	130.66	80.65	11
GRAND TOTAL				224.4	117.68	

Total Bars	52
Net Weight (no wastage)	112.08 kg
Order Weight (with 5%)	117.68 kg
Total Order Length	224.4 m

Disclaimer. This bar bending schedule is auto-generated based on the inputs provided. Final dimensions, lap lengths, and detailing must be verified against site drawings and reviewed by a qualified structural engineer before steel fabrication. The issuing party accepts no responsibility for errors arising from incorrect input data or unverified use on site.